PROJECT PDF

Willemen Groep
Boerenkrijgstraat 133, BE - 2800 Mechelen
tel +32 15 569 965, groep@willemen.be

Railway infrastructure works - Uccle

Project Details

Activities
Civil Engineering
Bridges
Railway infrastructure & stations
Road construction
General roadworks

Contractors
Willemen Bouw

location
Horzelstraat 300
1180 Ukkel Belgium
Brussels BE

Client
Infrabel

Engineering Office
TUC Rail

Construction period
3 years 5 months

Start work
01-2011

End of work
06-2014

The project consisted of infrastructure work along the track bed platform where railway lines L124 and L26 intersect. Several bridge decks were renovated and noise barriers installed, including 2,000 m² of green walls. For the Moensberg station at Uccle, new platforms have been built. Simultaneous with these main works diverse road, bedding, demolition, earth- and sewerage works were performed.

Some figures:

- Earthworks: 50,500 m³.
- Steel delivered: 680 tonnes.
- Concrete TPG: 8,800 m³.

Willemen Bouw

Boerenkrijgstraat 133
2800 Mechelen, Antwerpen
(Belgium)
tel +32 3 450 77 00
bouw@willemen.be
www.willemen.be

Willemen Bouw was established on 30 April 2025 through the merger of Willemen Construct, Cosimco, Franki Construct and Tools.

© Willemen Groep