PROJECT PDF

Willemen Groep
Boerenkrijgstraat 133, BE - 2800 Mechelen
tel +32 15 569 965, groep@willemen.be

Storm water basin Vivaqua - Ganshoren

Project Details

Activities
Civil Engineering
Water engineering

Contractors
Willemen Bouw

location
Nestor Martinlaan 38
1083 Ganshoren Belgium
Brussels BE

Client
Vivaqua

Engineering Office
Agidens, Nico Terryn

Span
8m

Surface area above ground
2 555m²

Surface area subterranean
2 555m²

Construction period
1 year 8 months

Start work
02-2014

End of work
10-2015

Storm water reservoirs connected to the drainage system that can collect 10,000 m³ of water during heavy storms, relieving the pressure on sewers. Buffered water is discharged into one of the main collectors in Brussels, half using a gravitational outlet, the other half using pumps.

An automated system has been fitted whereby the mechanical elements (pumps, mixers, rinsing system, …) can function entirely automatically and can be operated from the owner's own offices. There is also a monitoring system allowing stream levels to be surveyed constantly from a distance.

Design:

- Length ±370m
- Breadth 8m
- Depth of 3.5 to 6m
- Underground, roofing plate is 1.5m below ground level

Construction method:

- Basin structure made of more than 1700 secant piles
- Concrete: 3500 m³
- Reinforcement: 620 tonnes

© Willemen Groep

- HDPE pipes: 1000 m - diameters 400-350
- 2 pumps 35

Willemen Bouw

Boerenkrijgstraat 133
2800 Mechelen, Antwerpen
(Belgium)
tel +32 3 450 77 00
bouw@willemen.be
www.willemen.be

Willemen Bouw was established on 30 April 2025 through the merger of Willemen Construct, Cosimco, Franki Construct and Tools.