

Willemen Groep

Boerenkrijgstraat 133, BE - 2800 Mechelen tel +32 15 569 965, groep@willemen.be

Ecoduct Kempengrens - Mol

Project Details

Activities

Civil Engineering Bridges

Contractors

Willemen Construct

location

E34 kilometerpaal 57.8 2400 Mol Belgium Antwerpen BE

Client

Agentschap Natuur en Bos, Agentschap Wegen en Verkeer, Provincie Noord Brabant Nederland

Architects

Agentschap Wegen en Verkeer Afdeling expertise beton en staal

Engineering Office

Agentschap Wegen en Verkeer, afdeling expertise beton en staal

Span 68m

Surface area above ground 4 250m²

Surface area subterranean 2 870m²

Construction period 11 months

Start work 08-2013



Franki Construct built the 'Kempengrens' ecoduct [wildlife crossing] at the hamlet of Postel, in the municipality of Mol, which is near the Belgian-Dutch border. It is a bridge structure over the E34 that allows local fauna to get over the motorway in safety. The project is a collaboration between the Flemish and Dutch governments and aimed at reducing the negative impact on the local ecosystem caused by the man-made road infrastructure. The specific design and location of the bridge ensures maximum integration within the natural surroundings.

The minimum width of the ecoduct is 60 metres and it features a special diabolo-like design that continues on into the land abutments. The walls are arched and refer to the twisting movement of snakes, being one of the animal types that will make frequent use of the ecoduct. The bridge is constructed from reinforced, high-strength concrete (C40/50) and the land abutments from traditional, strong concrete (C35/40). The abutments have been conceived as a hollow volume, instead of a single, thick wall. The rounded shapes of the bridge, the hollow cavities in the abutments and the oval-shape of the central pillars demanded a specific type of shuttering. This ecoduct is certainly not a standard bridge. Throughout the period of the construction work it was essential that the E34 motorway remained open in the direction of Antwerp and Eindhoven with respectively two and one lanes.

Some key figures:

End of work 07-2014

32,000 m special fencing for fauna 15,000 m³ concrete 1,325,000 kg reinforcements 6,900 m pre-stressing (pipes) 90,000 m³ earth fill.

Willemen Construct



Boerenkrijgstraat 133 2800 Mechelen, Antwerpen (Belgium) tel +32 15 56 99 65 bouw@willemen.be www.willemen.be

Willemen Construct came into being on 1 July 2018 as a result of the merger between Willemen General Contractor and the construction department of Kumpen.